



MATERIAL LIST

QTY	DESCRIPTION	STOCK NO.	QTY	DESCRIPTION	STOCK NO.
1	METER BOX (18" X 36")	310060			
2	1" FIP X 1" PVC PACK JOINT CURB STOP	307369			
3 AS REQ.	1" PVC PIPE (SCHEDULE 40)	301016			
4	1" CORPORATION STOP (INLET 1" AWWA OUTLET PACK JOINT FOR 1" IPS PVC PIPE, FORD F1002 OR EQUAL)	307348			
5 AS REQ.	TRACER WIRE	211571			
6	18 INCH METER RING	310220			
7	18 INCH METER RING COVER	310130			
8	DIRECT BURY SPLICE KIT	211804			

GENERAL NOTES

- 1 IF WATER MAIN IS NOT 8" PVC, SEE WATER SERVICE CONNECTION STANDARD FOR OTHER MAIN TYPES. (CU_WS-301)
- 2 DURING SUMMER WEATHER, CONTRACTOR MAY INSTALL SAMPLE ASSEMBLY ABOVE GROUND.

**CONSTRUCTION STANDARD
CITY UTILITIES
OF SPRINGFIELD, MISSOURI**

**1" WATER SAMPLE
ASSEMBLY**