



MATERIAL LIST

QTY	DESCRIPTION	STOCK NO.	QTY	DESCRIPTION	STOCK NO.
1	18" X 36" METER TILE	310060			
2	3/4" FIP X 1" PVC PJ BRASS CURB STOP WITH LOCKING WING NUT	307366			
3	3/4" METER BRASS	307103			
4	3/4" X 5/8" METER	-----			
5	3/4" FIP X 1" PJ COUPLING	307135			
6	1" PVC SCHEDULE 40 PIPE	301016			
7	TRACER WIRE	211571			
8	METER RING	310220			
9	METER COVER	310130			
10	1" PJ x CUSTOMER PIPE SIZE PJ COUPLING	-----			

GENERAL NOTES

- 1 METER SHALL BE INSTALLED IN PARKWAY & LOCATED IN SUCH A POSITION SO AS NOT TO INTERFERE WITH SIDEWALK, DRIVEWAY, OR OTHER UTILITIES.
- 2 USE SUITABLE PIPE DOPE ON IP THEADED CONNECTIONS.
- 3 HEAT BEND.
- 4 TILE TO BE BLOCKED TO REQUIRED GRADE.
- 5 WOOD BLOCKS MUST BE A MINIMUM 2" X 6" X 18"

**CONSTRUCTION STANDARD
CITY UTILITIES
OF SPRINGFIELD, MISSOURI**

**TYPICAL 1" PVC WATER
SERVICE INSTALLATION WITH
5/8" METER**