



SU-PM

FRONT VIEW

SIDE VIEW

MATERIAL LIST

QTY	DESCRIPTION	STOCK NO.	QTY	DESCRIPTION	STOCK NO.
FURNISHED AND INSTALLED BY CUSTOMER			FURNISHED AND INSTALLED BY CITY UTILITIES		
1	1 CONCRETE PAD FOR PRIMARY METER CABINET (C.U. STANDARD PD-PMC-2) (SEE C.U. DESIGN DRAWING FOR DETAILS)		5	1 PRIMARY METER CABINET 200A	109057
2	3 LOAD BREAK ELBOWS (200 AMP) (CONNECTS LOAD SIDE PRIMARY)		6	6 LOAD BREAK BUSHING PLUG 200A	109326
3	1 GROUND ROD, 5/8" X 8'		7	3 LOAD BREAK ELBOWS (CONNECTS SOURCE SIDE PRIMARY)	
4	AS REQD CUSTOMERS PRIMARY CONDUCTOR (CUSTOMERS PRIMARY CABLE SHALL HAVE A NEUTRAL CONDUCTOR)		8	2 PADLOCK, LD-7	142433
			9	3 FAULT INDICATORS	109246
			10	4 DROP-IN ANCHOR 3/8"	102689
			11	3 CT, METERING TRANSFORMER	
			12	3 PT, METERING TRANSFORMER	
			13	AS REQD METER WIRING FROM PT'S & CT'S TO METER	
			14	AS REQD TEST SWITCHES (MOUNT INSIDE OF METER ENCLOSURE)	
			15	1 13 TERMINAL METER & BASE	

GENERAL NOTES

1. PENTA HEAD BOLT MUST BE INSTALLED AND SECURED AND PADLOCK MUST BE LOCKED BEFORE PRIMARY METER IS LEFT UNATTENDED.

**ELECTRIC SERVICE STANDARD
CITY UTILITIES OF SPRINGFIELD MO.**

DRAWN BY: G.G.	PRIMARY METER CABINET - 200A		
REV BY: K.DENTON			
FILE: SU-PM			
APPROVED: 11/06/06	REVISED: 5/29/2018	SHEET OF 1 OF 1	STD. NO. SU-PM