



MATERIAL LIST

QTY.	DESCRIPTION	STOCK NO.	QTY.	DESCRIPTION	STOCK NO.
FURNISHED AND INSTALLED BY CUSTOMER			FURNISHED AND INSTALLED BY CITY UTILITIES		
1	METER PEDESTAL FOR 8 TERMINAL METER (FREE STANDING, RAIN TIGHT ENCLOSURE MUST HAVE ROOM FOR TEST SWITCHES)		5	8 TERMINAL METER	
2	AS REQD METER BASE FOR 8 TERMINAL METER (RAIN TIGHT ENCLOSURE MUST HAVE ROOM FOR TEST SWITCHES)		6	BUSHING MOUNTED CURRENT TRANSFORMERS	
3	AS REQD SUPPORT STRUCTURE - ⚠		7	TEST SWITCH	
4	AS REQD 1" PVC METERING CONDUIT & CONNECTORS		8	METER SEAL	
			9	AS REQD CT TO TEST SWITCH WIRING	

GENERAL NOTES

- SEE CONSTRUCTION DRAWING FOR TRANSFORMER STANDARD BEING USED FOR THIS PROJECT.
- METER TO BE LOCATED NO CLOSER THAN 3' OR MORE THAN 40' FROM TRANSFORMER.
- METER BASE SUPPORT MUST BE STEEL.
- MINIMUM METER HEIGHT IS 30", MAXIMUM METER HEIGHT IS 48".

**ELECTRIC SERVICE STANDARD
CITY UTILITIES OF SPRINGFIELD MO.**

DRAWN BY: CK	SERVICE UNDERGROUND SINGLE PHASE TRANSFORMER MOUNTED CT'S IN TRANSFORMER
REV BY: W.BROOKS	
FILE: SU-T1-CT	
APPROVED: 09/18/06	REVISD: 08/19/02
SHEET OF 1 1	STD. NO. SU-T1-CT