



MATERIAL LIST

QTY.	DESCRIPTION	STOCK NO.	QTY.	DESCRIPTION	STOCK NO.
	FURNISHED BY CUSTOMER			FURNISHED AND INSTALLED BY CITY UTILITIES	
1	METER ENCLOSURE FOR 13 TERMINAL METER (RAINTIGHT ENCLOSURE MUST HAVE ROOM AND MOUNTING PLATE FOR TEST SWITCHES SIZE 12" X 18" HIGH X 4" DEEP) - ⚠⚠		2	13 TERMINAL METER	
			3	BUSHING MOUNTED CURRENT TRANSFORMERS	
			4	TEST SWITCH	
			5	METER SEAL	
			6	AS REQ'D CT TEST SWITCH WIRING	

⚠	GENERAL NOTES		ELECTRIC SERVICE STANDARD CITY UTILITIES OF SPRINGFIELD MO.			
	1.	CUSTOMER TO DELIVER METER BASE TO ELECTRIC METERING DEPARTMENT AT 742 N. BELCREST.	DRAWN BY:	SERVICE UNDERGROUND		
2.	CITY UTILITIES WILL ATTACH METER BASE TO TRANSFORMER.	REV BY:	THREE PHASE TRANSFORMER			
3.	TRANSFORMER TO SERVE SINGLE CUSTOMER ONLY.	FILE:	MOUNTED CURRENT			
		APPROVED:	SU-T3-CT	TRANSFORMER AND METERING		
		10/29/14	REVISED:	SHEET	STD. NO.	
			03/30/18	1 OF 1	SU-T3-CT	